



## FONTANA FIRE PROTECTION DISTRICT

8353 SIERRA AVE., FONTANA, CA 92335

Phone : 909.428.8890 Fax: 909.350.7676



### Provide the following notes on the plan:

NOTE #1: The Fontana Fire Prevention will require the following inspections and tests as a minimum:

- a. Weld inspection. Prior to installation of any pipe.
- b. Overhead installation and hydrostatic test. Prior to concealment of any pipe.
- c. Final sprinkler installation. All sprinkler alarms must be working prior to final inspections.  
Prior to calling a copy of the "Contractors Material and Test Certificate for Aboveground Piping" per NFPA shall be filed with this office.
- d. Contact the Fontana Fire Prevention bureau at 909-428-8890 48 hours in advance to schedule an inspection.

NOTE #2: The installation of the sprinkler system or modifications to existing sprinkler systems shall comply with:

- ☐ NFPA 13 2022 EDITION
- ☐ CALIFORNIA BUILDING CODE 2022 EDITION
- ☐ CALIFORNIA FIRE CODE 2022 EDITION

NOTE #3: Upon the completion of the sprinkler system the owner shall be provided with a copy of NFPA 25 attached to the riser in a protective sleeve or FACP cabinet.

NOTE #4: The Cp factor for determining sway brace loads shall be per 18.5.9 of NFPA 13, 2022 edition.

NOTE #5: All equipment shall be UL listed and approved for fire protection use.

NOTE #6: Automatic fire sprinkler system design shall be limited to 90 percent of the available water supply in calculated systems. Flow test must be within 6 months of fire sprinkler plans permit submittal date.

NOTE #7: All control valves and water flow switches on all sprinkler systems shall be electrically monitored at a Listed Central Receiving Station.

Note #8: Approved supervised indicating control valves shall be provided on each floor of all buildings at a location approved by the Assistant Fire Marshal.

Note #9: An audible device shall be provided at a normally occupied location and be provided with a sign stating, "SPRINKLER FIRE ALARM- WHEN ALARM SOUNDS CALL 9-1-1".

NOTE #10: The end sprinkler on a line shall be restrained against excessive vertical and lateral movement by use of a wrap-around U-hook or by other approved means per NFPA 13, 2022 Edition.

NOTE #11: All electrical rooms, upright sprinklers at the roof or in the attic space, or exterior sprinkler heads shall be of an intermediate head.

NOTE #12: When static pressure exceeds 100 psi arm mover and drops 12 inches and over requires a hanger.

NOTE #13: Lag screws or power-driven fasteners shall not be used to attach braces to the building structures.

NOTE #14: All piping and attached appurtenances subjected to system working pressure shall be Hydrostatically tested at 200 psi and shall maintain that pressure without loss for 2 hours.

NOTE #15: Sprinklers shall be installed in Elevator hoistways per NFPA 13 Section 9.3.6.1

NOTE #16: Where pipe is used for sway bracing, it shall have a wall thickness of not less than Schedule 40.

NOTE #17: All couplings from mechanical tees shall be attached to the pipe adjacent to the mechanical tee.

**The following notes shall be on the cover sheet and filled out entirely for all new and existing systems.**

### **Building Information**

Building Occupancy: \_\_\_\_\_ Square Footage: \_\_\_\_\_  
Construction Type: \_\_\_\_\_ Obstructed: \_\_\_\_\_ Non Obstructed: \_\_\_\_\_  
Ceiling Construction: \_\_\_\_\_ Obstructed: \_\_\_\_\_ Non Obstructed: \_\_\_\_\_

### **Fire Sprinkler Design Criteria**

(For All New and Existing Systems Including TI's)  
Hazard Classification: \_\_\_\_\_ Maximum Spacing: \_\_\_\_\_ Sq. Ft.  
Design Density: \_\_\_\_\_ Area in Square Feet: \_\_\_\_\_  
Flow @ Base of Riser: \_\_\_\_\_ @ PSI: \_\_\_\_\_  
System Size: \_\_\_\_\_ Sq. Ft Number of Heads: \_\_\_\_\_  
Sprinkler SIN#: \_\_\_\_\_ SR: \_\_\_\_\_ Temp: \_\_\_\_\_ QR: \_\_\_\_\_ Temp: \_\_\_\_\_  
(All sprinklers in tenant improvements shall be of the same response index and temperature)

### **Flow Test Information**

Date of Test: \_\_\_\_\_ Location: \_\_\_\_\_  
Elevation: \_\_\_\_\_ Site Elevation: \_\_\_\_\_ Tested By: \_\_\_\_\_  
Orifice Size: \_\_\_\_\_ in. Hyd Coef: \_\_\_\_\_ Pitot Pressure: \_\_\_\_\_ PSI  
Static Pressure: \_\_\_\_\_ Residual Pressure: \_\_\_\_\_ PSI @ \_\_\_\_\_ GPM

PLEASE SHOW ON THE PLAN:

