



FONTANA FIRE PROTECTION DISTRICT

8353 SIERRA AVE., FONTANA, CA 92335

Phone : 909.428.8890 Fax: 909.350.7676



HIGH PILE STORAGE

Fontana Fire Prevention Notes

The following notes are required for High Pile Storage:

Note #1: Call Fontana Fire Prevention 48 hours in advance 909-428-8890 to schedule an inspection.

The following inspections are required for approval of High Pile Storage:

- ☐ First Inspection – *Rough High Pile Storage Inspection*
- ☐ Second/Additional Inspections – *If needed*
- ☐ Third Inspection- *Final Approval*

Note #2: The installation of HIGH PILE STORAGE or modifications to existing HIGH PILE STORAGE shall comply with:

- ☐ NFPA 13 2022 EDITION
- ☐ CALIFORNIA FIRE CODE, 2022 EDITION
- ☐ Chapter 32 of the California Fire Code, 2022 Edition
- ☐ San Bernardino County Fire Standards, S-1.

Note #3: High Pile Storage consultant shall be on-site at time of Rough HPS inspection. Full size printed copy of HPS plans shall be provided. Consultant shall give education & training to business during rough inspection.

Note #4: At time of Rough High Pile Storage inspection, NO PRODUCTS shall be on racks that is scheduled for rough inspection. If required per approved plans, longitudinal and transverse flue keepers shall be installed at time of rough inspections. If required by approved HPS plans, transverse flue keepers by means of stickers, shall be installed.

Note #5: At time Rough High Pile Storage Inspection, if approved HPS plans indicate floor storage, permanent floor markings shall be in place per San Bernardino County Fire Standards & Approved High Pile Storage Plans, to show location(s) of palletized floor storage. No Products shall be in place during Rough HPS inspection.

Note #6: At time of initial Rough HPS inspection, if additional rough inspections are required, Fire Inspector as the authority to require HPS Consultant to be on-site for future rough inspections. Additional Rough inspection may be needed/required depending on circumstances and will be handled in Phases. Fire Inspector will provide additional requirements and details at time of initial Rough Inspection.

Note #7: FINAL Inspection: palletized products, hand stacking, floor storage, etc., permitted to be in building as called out on approved High Pile Storage plans. High Pile Storage consultant shall be on-site at time of FINAL inspection.